



ST LAWRENCE ENGINEERING DPC

745 GRAVES STREET, CLAYTON NEW YORK 13624

315/783.6384 • 315/408.7443

www.fourthcoast.com - www.stlawrenceengineering.com

**LEWIS COUNTY
PUBLIC SAFETY BUILDING
GENERATOR REPLACEMENT**

Addendum No. 2

26 January 2026

This addendum will be included in and made part of the Contract Documents.

1. Reference Contract Documents:

- A. CLARIFICATION:** Refer to Sheet C-100. The 8' tall chain link fence shall be 3 sided with the building acting as the fourth border. The fence shall be galvanized steel coated chain link fabric with galvanized steel framework and fittings. Post spacing, sizing, and foundation design shall be by manufacturer and designed for a Risk Category 4 facility. Chain link fabric shall be 2" mesh with 9 gauge core. Privacy slats shall be PVC or HDPE. Privacy Slat color to match is green. Provide standard color selection chart to engineer for approval.
- B. CLARIFICATION:** Refer to sheet C-100: Existing Outdoor Fuel Tank to be removed and turned over to Owner. Existing Pavilion / Shelter and concrete pad to be removed from site by Contractor.
- C. CLARIFICATION:** Refer to Sheet E-100: Existing Day Tank to be removed and turned over to Owner.
- D. CLARIFICATION:** Refer to Sheet E-100: Owner to provide fuel for Generator during construction to include during service entrance modifications. During shutdown of service entrance, Contractor is only required to maintain power to systems already connected to emergency power.

Respectfully,

ST. LAWRENCE ENGINEERING DPC

Robert J. Campany, PE

Copy: Matt O'Connor, Buildings and Grounds Supervisor, Lewis County